

MARINA DRIVE INFRASTRUCTURE IMPROVEMENTS

WHAT UTILITIES IS THE AUTHORITY CONSTRUCTING

Seacoast Utility Authority is replacing the 6-inch and 8-inch water main and 4-inch force main between Yacht Club Dr and the northern cul-de-sac along Marina Drive that has reached the end of its useful life.

PROJECT BREAKDOWN

- ✓ Installation of approximately 770 linear feet of 6-Inch and 560 linear feet of 8-inch ductile iron water main installed via open-cut
- ✓ Installation of approximately 470 linear feet of 6-inch C-900 PVC force main installed via open-cut
- ✓ Minimal disruption of existing services

Coordination with Village of North Palm Beach's Drainage Project that Includes:

- ✓ Installation of new drainage inlets in low-lying areas and the cul-de-sac
- ✓ Milling and resurfacing of Marina Drive with clearly defined project limits and updating road striping and signage
- ✓ Development of a traffic control plan to maintain marina access and parking during construction
- ✓ Installation of a new sidewalk on the west side of Marina Drive, north of Harbor Towers

WHAT THIS MEANS FOR YOU

- **Traffic impacts:** lane closures and detours may affect daily routes
- **Marina access:** Access to boats and parking may be restricted. We will provide advanced notice of any major impacts and restrictions.
- **Increased Noise:** Construction may produce noticeable noise during the day. Construction shall be limited to 8 AM - 5 PM Monday - Friday

PROJECT TIMELINE

SEACOAST UTILITIES

- Estimated 6 Months of Actual Construction
- Projected Start Date: **October 2025**



Contact Us



Capital Projects Coordinator
Seacoast Utility Authority
Brian Keilty
BKeilty@sua.com



Resident Engineer
Holtz Consulting Engineers
Kelley Conboy
Kelley.Conboy@holtzconsulting.com